# LONG RANGE PROPAGATION OF SPHERICAL SHOCKWAYES FROM EXPLOSIONS IN AIR

Prepared by: D. L. Lehto R. A. Larson

ABSTRACT: Hydrocode calculations for spherical shock propagation using the artificial-viscosity method are carried out to 0.2 psi overpressure for a nuclear explosion and for a TNT explosion. An ideal-gas integration from the literature is used to extend the results to  $1.6 \times 10^{-4}$  psi. Below 1.0 psi, 1 kt nuclear isequivalent to 0.7 kilotons of TNT.

PUBLISHED 22 JULY 1969

Air/Ground Explosions Division
Explosions Research Department
U. S. NAVAL ORDNANCE LABORATORY
White Oak, Silver Spring, Maryland 20910

22 July 1969

NOLTR 69-88

LORIG-RANGE PROPAGATION OF SPHERICAL SHOCKWAVES FROM EXPLOSIONS IN AIR

Although there has been occasional interest in using analytical techniques to predict explosion shockwave pressures out to large distances, there has been little emphasis on employing modern computer techniques to provide such predictions. Use of nuclear explosions for peaceful purposes—such as digging a canal—requires accurate evaluation of possible airblast damage among other considerations. A necessary part of the airblast evaluation is an accurate free-air pressure-distance curve for explosions. This report presents results obtained toward that end for both nuclear and for TNT explosions.

This investigation was sponsored jointly by the Defense Atomic Support Agency (under RIN 1004, Work Unit 1027) and by the Atlantic-Pacific Interoceanic Canal Feasibility Studies Program (Nuclear Safety Program—Acoustic Wave Effects Project).

JOHN C. DOHERTY

Captain, USN Commander

C. J. ARONSON

By direction

## NOLITA 69-88

## CONTENTS

		Page
1.	INTRODUCTION	ı
2.	THE PRESENT CALCULATIONS	1 1 1
3.	EXTENSION OF PRESENT CALCULATIONS	5 5 5
4.	EFFECTIVE BLAST YIELDS	3
5.	COMPARISONS WITE EXPERIMENT	4
6.	CONCLUSIONS	5
REF	TRENCES	6
Tab	TABLES	
1	Peak Overpressure vs Radius	8
	FIGURES	
1	Peak Overpressure vs Mistance for 1 kt Nuclear Explosion in Sea Level Real Air	
2	Peak Overpressure vs Distance for 1-1b TNT at Sea Level	
3	Logarithmic Slope of Overpressure vs Distance Curves	
4	Effective Blast Yield of Nuclear Relative to TNT	
5	Effective Blast Yield of Nuclear Explosion in Real Air Relative to Ideal Air	

#### 1. INTRODUCTION

In the past, most hydrocode calculations for explosions in real air were stopped at shock overpressures near 1.0 psi either because of numerical difficulties or because of lack of interest in such low pressures. In this report we discuss calculations that we have carried out to about 0.2 psi.

We are concerned here only with sea-level, free-air explosions; i.e., explosions that occur in an infinite volume of air at one atmosphere pressure and 15°C. Results for this uniform-atmosphere situation are of interest because they can be used as base data for calculations including atmospheric perturbations.

#### 2. THE PRESENT CALCULATIONS

#### 2.1 Nuclear Explosion

A homogeneous-sphere model is used for the explosion. The initial condition is a quiescent sphere of heated real air 4.251 meters in radius, at ambient density (0.001225 g/cm³) and containing LKT (10<sup>12</sup> calories) of internal energy. The solution to this initial-value problem is generated by the WUNDY hydrocode (ref. 1), with changes to the rezoning routine, a more accurate equation of state for air, and double precision in critical quantities. A zone size of two meters was used in the shock wave. To prevent excessive rounding of the shock front, the linear viscosity was decreased as the shock became weaker.

The calculated overpressure vs distance data are given in columns 1 and 4 of Table I and in Figure 1. (The calculations were stopped at 0.2 psi because of high computer cost.) These data are in satisfactory agreement with nuclear test data over the range 104 to 7 psi as shown on Figure 1 of ref. 2a for earlier WMDY calculations. Below 10 psi the present calculations are found to agree with the aircraft curve of Figure 3.3-7 of ref. 2b. Figure 1 also shows the lower end of the theoretical Problem M curve (ref. 3).

### 2.2 THT Exclosion

A similar calculation was made for a one-pound sphere of TNT. The conditions inside the charge at the time the detonation wave reaches the surface were calculated from the spherical Taylor wave with the LSZK equation of state for the explosion products (ref. 4). These calculations are similar to those reported in reference 5 except that a more recent equation of state for air was used and the calculation was carried much further (ref. 5 stopped at 2.5 psi). A zone size of one cm was used in the shock wave.

The calculated overpressure vs distance data are given in columns 1 and 5 of Table I and in Figure 2.

#### 3. EXTENSION OF PRESENT CALCULATIONS

3.1 Soviet Calculations

The problem of a nuclear explosion in ideal air (gamma=1.4) has been calculated by Brode (ref. 6), by Goldstine and von Neumann (ref. 7), and by Okhotsimskii, et al (ref. 8). All of these calculations stop near 1.0 psi. Brode used the artificial viscosity method. References 7 and 8 used shock fitting. All of these solutions are in excellent agreement. We also calculated this problem with WUNDY to about 1.0 psi to verify our method of calculation and found excellent agreement with these previous solutions.

The ideal air situation is of interest here because the calculation of reference 8 was extended by Okhotsimskii and Vlasova (ref. 9) to a very large distance (to 0.00016 psi). They continued to use shock fitting but rewrote the difference equations for the flow behind the front in terms of overpressure, overdensity, etc. to avoid numerical difficulties. (We did the equivalent thing by using double precision in our calculations.) The solution in reference 9 was carried to 0.03 psi, where it was stopped by numerical instabilities. It was carried further by an approximate method of Khristianovich. The net result was a numerical solution out to 0.00016 psi. The numerical values for overpressure vs radius are given in columns 1, 2 and 3 of Table I. The logarithmic slope of the pressure vs distance curve is shown in Figure 3. The slope has the point source value of -3.0 near the explosion and gradually approaches -1.0 at low pressures. Figure 3 also shows the slope for the present real-air calculations.

We will use this Okhotsimskii-Vlasova solution for <u>ideal</u> air to extend our present calculations for <u>real</u> air.

3.2 Asymptotic Behavior

The problem of propagation of a spherical shockwave to very large distances has been considered by Kirkwood and Bethe (ref. 10), by Landau (see ref. 11), and by Whitham (ref. 12), all of whom arrived at the following asymptotic formula for decay of peak overpressure:

$$\Delta P = A \left[ br \sqrt{\ln(br)} \right]^{-1}$$
 (1)

where  $\Delta P$  is peak shock front overpressure, r is radial distance from the origin to the shock front, and A and b are constants. This equation arises from an argument based on the logarithmic divergence of the characteristics behind the shock front. Equation (1) has been used by Miles (ref. 13) to extend the numerical calculations of Brode (ref. 14) to very low pressures.

This equation is consistent with the Okhotsimskii-Vlasova solution; we were able to fit their calculated results within one percent for the range below 0.4 psi.

We have not used this equation in the results we give in this report. It has been used here only as a check on the asymptotic behavior of the Soviet calculation.

#### 4. EFFECTIVE BLAST YIELDS

Each of these calculations obeys yield scaling exactly; i.e., the radius at which a given overpressure occurs is proportional to the cube root of the explosion energy. However, the three different types of explosions considered here (nuclear in ideal air, nuclear in real air, and TNT in real air) all give different amounts of dissipation near the source and thus have different amounts of energy available for the far-out blast wave.

We can compare the "effective blast yields" of two explosions by simply noting the distances at which a given overpressure occurs. The farther an explosion is able to give a given overpressure, the greater its effective yield. The effective yield ratio (at a given overpressure) of two explosions is simply the cube of the distance ratio. Figure 4 shows the effective blast yield of the calculated lKT nuclear explosion vs to calculated one pound TNT explosion scaled to two million pounds, both in real air. The line is drawn by eye through the calculated points. The effective yield varies with overpressure, as expected, since the pressure-vs-distance curves are not parallel. The effective yield appears to settle down near 0.7 below 1.0 psi\*. This gives an energy equivalence, for explosions in real air:

0.7 kilotons TNT = 1.0KT nuclear (below 1.0 psi).

In a similar way, the ideal nuclear explosion can be compared with the real-air nuclear explosion. Figure 5 shows the effective yield. The energy equivalence at low pressures is:

0.71KT nuclear, ideal air = 1.0KT nuclear, real air (below 7.0 psi).

Figure 5 also shows the energy equivalence for the Problem M calculation (ref. 3). Problem M takes an upward turn near 2.0 psi.

If we assume that these effective yields remain constant (i.e., that the overpressure vs distance curves remain parallel) for all overpressures below 0.2 psi, we can extend the real-air calculations by using the ideal-air results with the appropriate effective yield. To get the nuclear real-air distances, we multiply the ideal-air distances by  $(0.71)^{1/3} = 0.892$ . To get the distances in meters for one pound of TNT, we multiply the ideal-air distances for 1 kiloton of TNT, we multiply the ideal-air distances by  $(0.71/0.70)^{1/3} = 1.005$ .) The "extended" pressure vs distance data are shown in columns 4 and 5 of Table I beginning at 0.1927 psi and are marked by asterisks.

<sup>\*</sup>The well-known value of 0.5 in the 5-50 psi range comes from TNT data that lie about 15 per cent above the curve of Figure 2.

#### 5. CCMPARISONS WITH EXPERIMENT

The agreement of the nuclear real-air calculation with experimental frec-air data (not shown here) is satisfactory in the 0.1-100 psi region.

For high explosives, the only available free-air data below 0.1 psi are from Project BANSHEE. The BANSHEE events were 500-1b pentolite (not TMT) spheres detonated at altitudes up to 103,000 feet. Microbarograph measurements were made at the ground by Sandia and by BRL. The Sandia data (ref. 15) are shown on Figure 2. The slant range divided by  $(500)^{1/3}$ = 7.94 is plotted against measured reflected overpressure divided by two to convert it to incident overpressure. These events took place in non-sea level ambient conditions. The use of slant range versus overpressure corresponds to assuming that modified Sachs scaling holds (ref. 16).

The BANSHEE data are quite near the theoretical curve (Fig. 2).

Some surface-burst data are available in the 0.003-1 psi range. It is not necessarily appropriate to compare free-air pressures with surface-burst pressures measured near the surface. However, two sets of surface burst data are shown for comparison in Figure 2.

BRL surface burst data: These data are pressure-gage measurements (ref. 17) from 5, 20, and 100 ton surface bursts in Canada in 1959-61. The charges were formed of TNT blocks stacked on the ground to form a hemisphere. The plotted distances have been divided by  $(2 \text{ W})^{1/3}$  to reduce them to one pound in free air. (The factor of 2 used here is for a rigid surface and does not allow for close-in energy losses to the ground. This number may be as low as 1.5, depending on which free-air data are used in obtaining it. The exact value does not matter for our purposes.)

NOL micro-ton surface burst data: The dashed line on Figure 2 is a fit to 145 pressure-gage measurements (ref. 18) from surface-burst #6 electric blasting caps having an equivalent yield of 0.44 grams TMT:

$$\Delta_{\rm p} = 8.21~{\rm R}^{-1.42}$$

where  $\Delta p$  is overpressure in psi and R is radius in feet. The plotted distances have been divided by  $(2 \text{ W})^{1/3}$  to reduce them to one pound in free air.

The surface-burst data agree quite well with the calculated free-air curve down to about 0.2 psi. Below 0.2 psi the surface-burst data have a much faster rate of decay of pressure with distance than does the free-air calculation. This may be a real difference between surface bursts and free-air bursts due to energy losses from drag at the shock wave-ground interface. However, it should be pointed out that Forzel (ref. 19) has developed a free-air shock propagation theory that disagrees with the present calculations and agrees very well with the surface burst data.

### 6. CCNCLUSIONS

Hydrocode calculations have been carried out to 0.2 psi and extended to 0.00016 psi for a nuclear explosion in real air and for a TNT explosion in real air. The resulting pressures agree well with data near 0.001 psi from high altitude explosions of pentolite spheres.

#### REFERLICES

- 1. D. Lehto and M. Lutzky, "One-Dimensional Hydrodynamic Code for Nuclear Explosion Calculations," U. S. Naval Ordnance Laboratory NOLTR 62-168, DASA 1518, AD615801, Mar 1965
- 2a. L. Rudlin, "Hydrodynamic Calculations of the Shockwave from Nuclear Explosions at Sea-Level Altitude of Burst," U. S. Naval Ordnance Laboratory NOLTR 62-152, DASA 1361, Sep 1962
- 2b. J. F. Moulton, Jr., "Muclear Weapons Blast Phenomena," U. S. Naval Ordnance Laboratory, DASA-1200, Mar 1960, Volume 1. Secret Restricted Data
- 3. C. D. Broyles, "IBM Problem M Curves," Sandia Corporation SCTM 268-56-51, Dec 1956
- 4. M. Lutzky, "The Flow Field Behind a Spherical Detonation in TNT Using the Landau-Stanyukovich Equation of State for Detonation Products," U. S. Naval Ordnance Laboratory NOL TR 64-40, Dec 1964
- 5. M. Lutzky, "Theoretical Versus Experimental Results for Airblast from One-Pound Spherical TRT and Pentolite Charges at Sea Level Conditions," U. S. Naval Ordnance Laboratory NOL TR 65-57, Jul. 1965
- 6. H. L. Brode, "Point Source Explosion in Air," Rand Corporation RM-1824-AEC, Dec 1956
- 7. H. H. Goldstine and J. von Neumann, "Blast Wave Calculation," Comm. Pure Appl. Math. 8, 327, 1955
- 8. D. Ye. Okhotsi skii, I. L. Kondrasheva, Z. P. Vlasova, and R. K. Kazakova, Tr. Mat. in-ta. Akad. Nauk SSSR 50, 1, 1957
- 9. D. Ye. Okhotsimskii and Z. P. Vlasova, "The Behavior of Snock Waves at Large Distances from the Point of Explosion," <u>USSR Computational Mathematics and Mathematical Physics 1, 107, 1963</u>
- 10. J. G. Kirkwood and H. A. Bethe, OSRD No. 588, in W. W. Wood, Shock and Detonation Waves, John Gamble Kirkwood Collected Works, Gordon and Breach, N. Y., 1967
- 11. L. I. Sedov, Similarity and Dimensional Methods in Mechanics, Academic Press, N. Y., 1959, pp 295-304
- 12. G. B. Whitham, "On the Propagation of Weak Shock Waves," J. Fluid Mech. 1, 290, 1956
- 13. J. W. Miles, "Decay of Spherical Blast Waves," Phys. Fluids 10, 2706, 1967
- 14. H. L. Brode, "Blast Wave from a Spherical Charge," Phys. Fluids 2, 217, 1959
- 15. J. W. Reed, personal communication
- 16. M. Lutzky and D. Lehto. "Shock Propagation in Spherically Symmetric Exponential Atmospheres," Phys. Fluids 11, 1456, 1968

- 17. C. N. Kingery and B. F. Pannill, "Peak Overpressure vs Scaled Distance for TNT Surface Dursts (Hemispherical Charges)," Ballistic Research Laboratories Report No. 1518, Apr 1964, AD 443102
- 18. L. Sadwin, personal communication
- 19. F. Porzel, personal communication

Table I

Peak Overpressure Vs Radius

Overpressure	Cverpressure	Ideal Nuclear	Real Nuclear	1-1b THT
(psi)	(bars)	Redius (km)	Radius (km)	Radius (m)
05/00				•
25600.	1765.	0.01548		
21660.	1493.	.01637		
18470.	1274.	.01726		
14420.	994.4	.01875		
11470.	791.2			
11470.	171.2	.02024		
9281.	639.9	0.02172	0.0192	
7616.	525.1	.02321		
6326.			.0204	0.042
	436.2	.024.69	.0215	.054
5313.	366.3	.02618	.0227	.067
4506.	310.7	.02766	.0240	.082
2071				- -
3854.	265.8	0.02915	0.0252	0.097
3138.	216.4	.03123	.0268	.120
2394.	165.0	.03420	.0292	.154
1868.	128.8	.03718	.0314	
1487.	102.5	.04015		.185
2401.	102.7	•04072	.0339	,219
1204.	83.00	0.04312	0.0362	0.050
989.3	68.21	.04609		0.250
823.3	56.77	• • •	.0385	.285
692.9		.04907	.0410	.318
	47.77	.05204	.04.35	<b>.</b> 350
589.1	40.62	.05501	.0450	.380
505.3	34.84	ח חבוה	0.0105	
		0.05798	0.0485	0.412
413.4	28.50	.06214	.0520	.458
317.8	21.91	.06809	.0575	.519
250.4	17.26	.07404	.0624	.580
201.5	13.89	.07999	.0687	.642
			10001	• OCE
165_1	11.39	0.08594	0.0740	0.700
137.5	9.487	.09189	.0789	.760
116.1	8.006	.09784	.0846	
99.27	6.844	.1038		.810
85.79			.0892	.875
0).17	5.915	.1097	.0946	.910
74.87	5.162	0.1157	0.0997	0.055
62.78				0.955
	4.329	.1240	.1069	1.02
50.08	3.453	.1359	.1182	1.14
40.97	2,825	.1479	.1295	1.25
34.22	2.359	.1598	.1404	1.35
29.09	2.006	0.1717	0.1516	1.45
21.93	1.512	.1956	.173	1.65
19.38	1.336	.2075	.184	
17.28	1.191	.2194		1.75
13.56		- ·	.194	1.84
±√•√€	0.9347	.2481	.221	2.08
		^		

Table I (Cont'd)

Overpressure (psi)	Overpressure (bars)	Ideal Nuclear Radius (km)	Real Nuclear Radius (km)	1-1b TNT Radius (m)
11.38	0.7847	0.2719	0.243	2.27
9.743	.6718	.2958	.265	2.45
8.474	.5843	.3196	.284	2.63
7.468	.5149	.3435	•307	2.82
6.654	.4588	.3673	.329	3.00
5.426	0.3741	0.4150	0.370	3.39
4.549	.3137	.4627	.413	<b>3.77</b>
4.074	.2809	.4960	.442	4.01
3.533	.2436	.5436	.489	4.40
3.109	.2144	.5912	.520	4.76
2.769	0.1909	0.6389	0.562	5.15
2.491	.1717	.6865	.603	5.50
2.065	.1424	.7818	.695	6.30
1.899	.1309	.8294	.731	6.67
1.586	.1093	.9437	.836	7.60
1.390	0.09585	1.039	0.922	8,4
1.235	.08518	1.134	1.01	9.1
1.110	.07655	1.228	1.09	9.8
1.007	.06942	1.323	1.18	10.7
0.9202	.06345	1.417	1.265	11.4
0.8466	0.05837	1.510	1.35	12.18
.7283	.05022	1.697	1.52	13.66
.6377	.04397	1,884	1.68	15.08
.5662	.03904	2.070	1.85	16.66
.4609	.03178	2.441	2.18	19.60
0.3873	0.02670	2.811	2.51	22.54
.2917	.02011	3.549	3.17	28.37
.2326	.01604	4.286	3.82	34.09
.1927	.01329	5.022	*4.48	39.76
.1641	.01131	5 <b>.</b> 757	*5.14	*45.9
0.1426	0.009830	6.492	*5.79	*51.8
.1125	.007757	7.960	*7.10	*63.5
.09258	.006383	9.427	*8.41	*75.2
.07845	.005409	10.89	*9.71	*86.9
.06793	.004683	12.36	*11.03	<del>*</del> 98.6

<sup>\*</sup> Scaled from the ideal nuclear data.

Table I (Cont'd)

Overpressure (psi)	Overpressure (bars)	Ideal Nuclear Radius (km)	Real Nuclear Radius (km)	1-1b TNT Radius (m)
0.05981	0.004124	13.82	*12.33	*110.3
.04813	.003318	16.75	#14.94	*133.7
.04015	.002769	19.68	*17.55	*157.0
.03438	.002370	22.61	*20.2	*180.
.03001	.002069	25.54	*22.8	#204.
0.02659	0.001834	28.47	<b>*</b> 25.4	*227.
.02318	.001598	32.13	*28.7	*256.
.01846	.001272	40.91	*36.5	*326.
.01526	.001052	46.76	*41.7	*373.
.01076	.0007416	64.32	*57.4	*513.
0.007659	0.0005281	87.73	<del>*</del> 78.2	<b>*</b> 700.
.004813	.0003318	134.5	<b>*120.</b>	*1073.
.002880	.0001986	216.5	*193.	*1728.
.001684	.0001161	356.9	*318.	<b>*</b> 2850.
.0007337	.00005058	778.2	*694.	*6210.
0.0001639	0.00001130	3212.	*2865.	*2560c.

<sup>\*</sup> Scaled from the ideal nuclear data.




FIG. 1 PEAK OVERPRESSURE VS DISTANCE FOR 1KT NUCLEAR EXPLOSION IN SEA-LEVEL REAL AIR SHEET 1




FIG. 1 (CONTINUED) SHEET 2




FIG. 2 PEAK OVERPRESSURE VS DISTANCE FOR 1-LB TNT AT SEA LEVEL SHEET 1





FIG. 2 (CONTINUED) SHEET 2






FIG. 4 EFFECTIVE BLAST YIELD OF NUCLEAR RELATIVE TO TNT




FIG. 5 EFFECTIVE BLAST YIELD OF NUCLEAR EXPLOSION IN REAL AIR RELATIVE TO IDEAL AIR

UNCLASSIFIED

Security	

(Security classification of title body of abstract and indexi	NIRCL DATA - R&D	red when t	the overall report is classified)
1 ORIGINATING ACTIVITY "Corporate author"	2	. REPO	ST SECURITY CLASS FICATION
U. S. Naval Ordnance Laboratory	) 		UNCLASSIFIED
White Oak, Silver Spring, Maryland 20	910	6 GROU	
3 REPORT TITLE			
	ACCULATION TENNS TO	\T AC *A~	10 701 177
ICNG RANGE PROPAGATION OF SPHERICAL SHO	canhyed from Exp	TOSTOR	io Tii VTK
4 DESCRIPTIVE NOTES (Type of report and inclusive deser)			
S AUTHOR(S) (Last name lirst name initial)			
Lehto, D. L.			
Larson, R. A.			
6 REPORT DATE	TA TOTAL NO OF PA	SES	76 NO OF REFS
22 July 1969	20		18
BE COLIRACT OR GRANT NO	90 DRIGINATOR'S REF	AUK TRC	3EQ(\$:
a paosect no RLN 1004, Work Unit 1027	NOLITR 6	9-88	
c	SP OTHER REPORT N	O(5) (Any	other numbers that may be essigned
	this report)		
d 10 AVAILABILITY/LINIFATION HOTICES	<u> </u>		
	<b>L14</b>		44. 34.4.42.44
This document has been approved for pulis unlimited.	oii: Leiesse sud	saie,	its distribution
11 SUPPLEMENTARY NOTES	12 SPONSORING HILIT	ARY ACT	VITY
	Defense Atom	ic Sup	port Agency
13 ABSTRACT	سوطعد كالإلباء مختلف سي		~3~1
Judananda aslaulations for enhances	l shook name on the	ion not	ing the switters.
Hydrocode calculations for spherical viscosity method are carried out to 0.2			_
and for a TMT explosion. An ideal-gas			
extend the results to 1.6 x 10-4 psi. I			
to 0.7 kilotons of TNT.			
Tanah.			
DD FORM 1/172		iDa	CLASSIFIED

Security Classification

KE WORDS	LIN	LINK A		LINK B		LINK C	
	KOLE	wT	ROLE	WT	ACLE	₩T	
Explosions							
Shock Waves							
Airblast Damage		1			í i		
Nuclear Explosions			! :				
Computerized Simulation					! !		
					i		
					i l		
			¦ ¦				
	ļ		!				
	<b>,</b>						

#### INSTRUCTIONS

- ORIGINATING ACTIVITY. Enter the name and address of the contractor, subcontractor, grantee, Department of De-fense activity or other organization (corporate euthor) issuing the report.
- 2s. REPORT SECURITY CLASSIFICATION: Enter the overall security classification of the report. Indicate whether "Restricted Data" is included. Marking is to be in accordance with appropriate security regulations.
- 26. GROUP: Automatic downgrading is specified in DoD Directive 5200.10 and Armed Forces Industrial Hanual. Enter the group number. Also, when applicable, show that optional markings have been used for Group 2 and Group 4 as author-
- 3. REPORT TITLE: Enter the complete report title in all capital letters. Titles in all cases should be unclassified. If a meaningful title cannot be selected without classification, show title classification in all capitals in parenthesis immediately following the title.
- 4. DESCRIPTIVE NOTES: It appropriate, enter the type of report, e.g., interim, progress, summary, annual, or final. Give the inclusive dates when a specific reporting period is
- S. AiTHOR(S). Enter the name(s) of author(s) as shown on or in the report. Enter less name, first name, middle initial. If military, show rank and branch of service. The name of the name the principal author is an absolute minimum requirement.
- 6. REPORT DATE. Enter the date of the report as d-y, "month, year, or month, year, if more than one date appears on the report, use date of publication.
- TOTAL NUMBER OF PAGES: The total page count should follow normal pagination procedures, i.e., enter the number of pages containing information.
- NUMBER OF REFERENCES. Enter the total number of references cited in the report.
- 8a. CONTRACT OR GRANT NUMBER. If appropriate, enter the applicable number of the contract or grant under which the report was written.
- 85, &c, & 8d. PROJECT NUMBER: Enter the appropriate military department identification, such as project number, subproject number, system numbers, task number, etc.
- 9a. ORIGINATOR'S REPORT NUMBER(S) Enter the offiand controlled by the originating activity. This number must be unique to this report.
- 95. OTHER REPORT NUMBER(S): If the report has been assigned any other report numbers (either by the originator or b) the sponsor), also enter this number(s).
- 16. AVAILABILITY/LIMITATION NOTICES Enter any limitations on further dissemination of the report, other than these

imposed by security classification, using standard statements such as:

(1) "Qualified requesters may obtain copies of this report from DDC."

- "Foreign announcement and dissemination of this report by DDC is not authorized."
- "U. S. Government agencies may obtain copies of this report directly from DDC. Other qualified DDC users shall request through
- (4) "U. S. military agencies may obtain copies of this report directly from DDC. Other qualified users shall request through
- "All distribution of this report is controlled. Qualified DDC users shall request through

If the report has been furnished to the Office of Technical Services, Department of Commerce, for sale to the public, indicate this fact and enter the price, if known.

- IL SUPPLEMENTARY NOTES: Use for additional explanatory notes.
- 12 SPONSORING MILITARY ACTIVITY: Enter the name of the departmental project office or laboratory sponsoring (paring for) the research and development. Include address.
- 13 ABSTRACT: Enter an abstract giving a brief and factual summary of the document indicative of the report, even though it may also appear elicathere in the body of the technical re-port. If additional space is required, a continuation sheet shall be attached

It is highly desirable that the abstract of classified reports be unclassified. Each paragraph of the abstract shall end with an indication of the military security classification of the information in the paragraph, represented as (TS) (S) (C), or (U)

There is no limitation on the length of the abstract. How-ever, the suggested length is from 150 to 225 words

14 KEY WCRDS: Key words are technically lacaningful terms or short phrases that characterize a report and may be used as index entries for cataloging the report. Key words must be selected so that no security classification is required. Identifiers, such as equipment model designation, trade name, military project code name, geographic location, may be used as key words but will be followed by an indication of technical context. The assignment of links, rules, and weights is optional.

UNULASSIFIED

Security Classification